





REV.	DESCRIPTION	DRAWN	CHECKED	APPROVED
A	NEW RELEASE	ZQJ 11/18/2014		

**NOTES:**  
 1. Insulation material: PVC  
 Color: Gray  
 4. Product Number Code  
 LL1049-3 - X X X X X X X X X X

- 2. SPECIFICATION**
- Rating: 150V
  - Conductor Size: 30AWG
  - Insulation resistance: 100MΩ/km min.
  - Contact resistance: 377Ω/km max.
  - Insulation thickness average: 7 mil.
  - Minimum insulation thickness : 6 mil.
- 3. APPLICATION**
- Internal wiring of computers, electronic exchanges, measurement control devices, business machines, communication devices, and other electronic equipment.
- 4. Product Number Code**
- Edge mark
  - R: Red mark
  - F: Flower mark
  - Wire type
  - A: Single Type
  - B: Stranded Type
  - Wire AWG
  - 30: 30AWG
  - Cable color
  - A: Gray
  - No. Of positions
  - 68: 68pin
  - 80: 80pin
  - 100: 100pin



No. of positions	Dimensions		Tolerance
	TP(mm)	W(mm)	
68	42.545	43.18	±0.25
80	50.165	50.80	±0.25
100	62.865	63.50	±0.25



GENERAL TOLERANCE	ANGLE TOLERANCE	PROJECTION	TITLE
X: ±0.60	X: ±5°	mm	UL2678 FLAT CABLE 0.635MM
.X: ±0.38	.X: ±3°	mm	
.XX: ±0.25	.XX: ±2°	mm	

DRAWING TYPE	CUSTOMER	SHEET	OF
SCALE	1:1	1	1
DRAWING NO.			

慈溪蓝翎电子有限公司  
 CIXI LANLING ELECTRONICS CO., LTD.

